










# MALABAR TWO-FOLD CONSTRUCTION SPECIFICATION

	<p><b>CONSTRUCTION</b></p> <p>MACHINE GAUGE PILE HEIGHT TUFT DENSITY PILE WEIGHT</p> <p>TOTAL CARPET WEIGHT CARPET THICKNESS WIDTH</p> <p>ISO 1766 ISO 1763</p> <p>ISO 8543 ISO 1765</p> <p>5/32nd Loop Pile 5 mm 89,279 loops/m<sup>2</sup> 1,017 gms/m<sup>2</sup> 30 oz/yd<sup>2</sup> 1,954 gms/m<sup>2</sup> 7.9 mm 4 &amp; 5 metre</p>
	<p><b>COMPOSITION</b></p> <p>PILE CONTENT PRIMARY BACKING SECONDARY BACKING</p> <p>ISO 1833</p> <p>100% Wool Woven Polypropylene Woven Secondary</p>
	<p><b>PERFORMANCE</b></p> <p>SUITABILITY WIRA ABRASION TEST STATIC LOADING DYNAMIC LOADING TUFT ANCHORAGE</p> <p>PD 6527:Clause 17 ISO 3416 ISO 2094 ISO 4919</p> <p>Extra Heavy Domestic / Medium Contract Exceeds 13,200 Rubs 28.6% Thickness loss after 24 hrs recovery 26.5% Thickness loss after 1,000 impacts Above 1kg</p>
	<p><b>COLOUR FASTNESS</b></p> <p>LIGHT FASTNESS WET FASTNESS SHAMPOO FASTNESS</p> <p>ISO 105-B02 ISO 105-E01 BS 1006:UK-TB</p> <p>5/6 on all colours 4/5 on all colours 4/5 on all colours</p>
	<p><b>THERMAL VALUE</b></p> <p>TOG VALUE THERMAL RESISTANCE</p> <p>ISO 5085-1</p> <p>1.2 Tog 0.12 m<sup>2</sup> k/w</p>
	<p><b>FLAMMABILITY</b></p> <p>CE MARK RATING HOT METAL NUT TEST METHENAMINE PILL TEST</p> <p>CE BS4790 ISO 6925</p> <p>Cfl, S1 Pass - Low radius of ignition Pass</p>
	<p><b>CHEMICAL IMPACT</b></p> <p>FORMALDEHYDE REACH CERTIFICATE</p> <p>CE</p> <p>E1 Compliant</p>
	<p><b>BIOLOGICAL ATTACK</b></p> <p>MOTH / INSECT RESISTANT</p> <p>Eulan Treated</p>
	<p>ANTI STATIC</p> <p>-0.3 kv (Requirement less than +2.0 kv)</p>

## GENERAL INFORMATION

**Installation** - In all contract locations an 'all over' stick down method is recommended to BS 5325 (1983). If underlay is required the carpet should be power stretched. For quantity orders requiring colour matching, please state at time of ordering.

**Maintenance** - Please note all pile carpets of any fibre type will flatten to some extent in traffic lanes although regular vacuuming will help to allay this. This 'flattening' is a normal reaction to localised traffic in both domestic and contract locations and is not a manufacturing fault, therefore will not be accepted as the basis for any claim. Rubber soled shoes when used constantly in heavy traffic areas can sometimes act abrasively on the surface of the carpet therefore it is recommended that their use is limited. Loop pile carpets should be vacuumed with a cylinder cleaner or suction head only. Occasionally wool may contain traces of the sheep's natural environment. These traces can be easily removed and do not affect the durability of the carpet. Joins in loop pile carpet can sometimes be visible, especially so in patterned loop pile. The use of seaming cement is advisable.

**Heather Shades** - In manufacturing heather shades several contrasting colours are blended to create a 'heather' yarn. As such random coloured flecks will be apparent in the carpet. These flecks form part of the effect and are not considered the basis for any claim.

**Matching** - This sample may not be from the same production batch as current stock and therefore should be used as a guide and not as an exact match. Equally matching between 4 & 5 metre widths cannot be guaranteed.

**Important** - A good quality underlay is always recommended when fitting a new carpet. Minimum order length 1.5 metres.

April 2016



**GREENWOOD & COOPE LTD.** Brookhouse Mill, Greenmount, Bury, Lancashire BL8 4HR  
 TEL: 01204 881234 FAX: 01204 887722  
 E-MAIL: info@cormarcarpets.co.uk WEBSITE: www.cormarcarpets.co.uk

